

715.40.2 - Type V Pavement Markings

Effective Date: February 24, 2009

Transverse Markings

Intersection Markings
Symbols
Legends
Stripes

| Material | Manufacturer | Approval Number |
|------------------------------|-----------------------|-----------------|
| 380-IES White and Yellow | 3M Corporation | 1380664A |
| 380-IES White and Yellow | 3M Corporation | 1393190 |
| Premark Plus White or Yellow | Flint Trading Company | 1380662A |
| Hot-Tape White or Yellow | Flint Trading Company | 1380663A |
| Premark Plus White or Yellow | Flint Trading Company | 1393188 |
| Hot-Tape White or Yellow | Flint Trading Company | 1393189 |

Note: Road surface must be pre-heated to and material must be heated to 400 degrees Fahrenheit and verified with a infrared heat thermometer when applying degrees Fahrenheit and verified with a infrared heat thermometer when applying

Zumar Industries Hot-Tape. 380-IES approved to be used for gore and lane shunt area stripes only.

Longitudinal Lines

Lane Lines
Edge Lines
Barrier Lines
Channelizing Lines

| Material | Manufacturer | Approval Number |
|------------------------------|------------------------------|-----------------|
| 381-IES White and Yellow | 3M Corporation | 1380665A |
| 381-IES White and Yellow | 3M Corporation | 1393191 |
| Premark Plus White or Yellow | Flint Trading Company(F129A) | 1380666A |
| Premark Plus White or Yellow | Flint Trading Company(F129A) | 1393192 |

Enhanced Skid Resistant Material

Enhanced Skid Resistant Material

Crosswalks

Other Markings as Specified

| Material | Manufacturer | Approval Number |
|---------------------------------------|------------------------------|------------------------|
| Premark Plus Vizigrip White or Yellow | Flint Trading Company(F129A) | 1393193 |

The contractor shall provide the engineer with certification from the marketing manufacturer that he/she has been adequately trained and certified to apply the manufacturer's material.

Enhanced skid resistant material shall be used for all crosswalks and other markings as specified in the project plans.